



William Street & Sidewalk Upgrades

CAPITAL IMPROVEMENT PROJECT

The Municipality of the District of West Hants has awarded a contract to Dexter Construction to overhaul William Street and Sidewalks in the community of Hantsport. The scope of work includes the following executable work plan:

1. Sawcut the edge of the roadway, excavate and remove existing curb and sidewalk on both sides of the street;
2. Place base and install new concrete curb along both sides of the street;
3. Place base install new 1.5 meter wide concrete sidewalk along the south side of William Street;
4. Cold plane existing roadway;
5. Grade roadway with existing material;
6. Reinstatement driveway aprons on back side of curb and asphalt at the face of the new curb;
7. Tack coat and re-pave roadway;
8. Reinstatement of lawns along the street (to be performed by WH Public Works staff).

Schedule:

Construction is scheduled to be completed before the end of June. Hours of work will generally be weekdays from 7 am to 7 pm. While construction is ongoing, the work area may be limited to one lane of through traffic or full street detours during work hours, causing some minor delays. It is anticipated that traffic control personnel will be utilized for the project.

Communication/Contacts:

The Municipality encourages open communication during construction projects, particularly in areas adjacent to your property. On site personnel will make every effort to keep residents informed and advised of scheduled interruptions for driveway access, whenever possible. We appreciate your understanding and patience. If you should have any questions or issues, please contact Karrie at Department of Public Works, 902-684-3219, kritchie@westhants.ca.